



مولانا آزاؑ نیشنل اردو یونیورسٹی

MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998  
(Accredited "A+" Grade by NAAC)



HY/ADMN/ENGG/2022/F365

Dated: 06-02-2023

Notice Inviting Quotation

NIQ No. 16 /MANUU/CD/2022-23/

Name of the Work	Provision for Pantry in stationary room at CSIT MANUU Campus.
Estimated Cost	Rs 37,000/-
Date of start of Bid Submission	06-02-2023
Last date & Time for submission of Bids	16-02-2023

  
Executive Engineer  




Name of the Work : Provision for Pantry in stationary room at CSIT MANUU Campus.

- 1) The estimate amount is inclusive of GST.
- 2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
- 3) The Bidder should intimate GST percentage separately.

SCHEDULE OF QUANTITIES

S.No.	Description of item	Qty	Unit	Rate		Amount
				In fig	In words	
1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.					
1.1	Cement mortar 1:3 (1 cement :3 coarse sand)	2.4	Sqm			
2	12 mm cement plaster of mix :					
2.1	1:6 (1 cement: 6 fine sand)	3	sqm			
3	15 mm cement plaster on the rough side of single or half brick wall of mix :					
3.1	1:4 (1 cement: 4 fine sand)	2.5	sqm			
4	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete in shelves including setting in cement mortar 1:3 (1 cement : 3 coarse sand), cost of required centering, shuttering and finishing with neat cement punning on exposed surfaces but excluding the cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand including manufactured sand derived from Recycled Concrete Aggregate (RCA) upto 20% : 3 graded stone aggregate 20 mm nominal size Recycled Concrete Aggregate (RCA) upto 20%).	0.17	cum			
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.					
5.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	30	kg			

Gachibowli, Hyderabad – 500 032.

☎ 8333853369 ☎ 040 23120600 Extn. 1360,1361 & 1362 ✉ Email:executive\_engineer@manuu.edu.in  
website: www.manuu.ac.in

*Handwritten signature*

6	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.					
6.1	Granite stone slab colour black, Cherry/Ruby red					
6.1.2	Area of slab over 0.50 sqm	2.5	sqm			
7	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :					
7.1	610x460 mm bowl depth 200 mm	1	each			
8	Providing and fixing P.V.C. waste flexible pipe of 40mm dia for sink or wash basin including P.V.C. waste fittings complete.					
8.1	40 mm dia	1	each			
9	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.					
9.1	15 mm nominal bore	1	each			
10	Providing and fixing PVC pipe of 40mm dia with all necessary fittings	5	metre			
11	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded					


	fittings, including fixing clamps at 1.00 m spacing. This includes jointing of pipes & fittings the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.					
11.1	Internal work - Exposed on wall					
11.1.2	20 mm nominal dia Pipes	5	metr e			
12	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	5.5	sqm			
13	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.					
13.1	Two coats	5.5	sqm			
14	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	2.5	sqm			



Less Rebate Offered( if any)	_____
Net Amount (excluding GST)	_____
Net Amount in words	_____
Add GST	_____
Total Amount (Including GST)	_____
words	Total Amount in

Term and conditions:

- 1) The work should be carried out strictly as per the specifications and as per the directions of the Engineer-in-charge.
- 2) Time allowed for completion of work is 10 days from the date of issue of Work Order.
- 3) The rate shall include the cost of all labour, materials and all the operations involved as described in the specification of item and nothing extra shall be paid on whatsoever account.
- 4) The rate should be quoted both in figures and words which should include all taxes etc.
- 5) The rate should be applicable to all heights and leads and transportation of materials and tools etc.
- 6) Defect liability period 1 (One) year from the date of completion of the work
- 7) The payment shall be made as per actual execution and measurement at site.
- 8) The Income tax shall be deducted as per applicable and notified by Govt.of India.
- 9) In case of delay in completion of the contract,LD at 1/2 percent of the contract value per day of delay subject to the maximum of 10% of contract value/work order will be levied without assigning any reason unless extension is obtained in writing from the office on valid ground before completion date.

  
Executive Engineer

Copy to :

- 1) The Office of the Registrar,
- 2) Director CIT for uploading in the University website.
- 3) Notice Board.