



مولانا آزاد نیشنل اردو یونیورسٹی

MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998
(Accredited "A+" Grade by NAAC)

Notice Inviting Quotation

NIQ No. 11 /MANUU/CD/2023-24/ dated : 10-07-2023

S.No	Name of the Work	Repair of damaged flooring in the shop 7 & 8 at Shopping complex in MANUU Campus, Gachibowli, Hyderabad
1.	Time Allowed for work completion	10 days
2.	Date of start of Bid Submission	10-07-2023 at 01:00 PM
3.	Last date & Time for submission of Bids	17-07-2023 at 10:00 AM

Details of Contractor/Firm

1.	Name of the Firm	
2.	Address	
3.	Phone	
4.	Email	
5.	Firm Registration	
6.	GST Registration	
7.	PAN Card No.	

Signature of Contractor with Stamp

Executive Engineer

कार्यकारी अभियंता/ Executive Engineer
इंजीनियरिंग अनुभाग/ Engineering Section
मौलाना आज़ाद नेशनल उर्दू यूनिवर्सिटी
Maulana Azad National Urdu University
गञ्जीबोली, हैदराबाद - ५०००३२
Gachibowli, Hyderabad-500 032.



Name of the Work : Repair of damaged flooring in the shop 7 & 8 at Shopping complex in MANUU Campus, Gachibowli, Hyderabad

- 1) The estimate amount is inclusive of GST.
- 2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
- 3) The Bidder should intimate GST percentage separately.

SCHEDULE OF QUANTITIES

DSR No.	Description of item	Unit	Qty	Rate		Amount
				In fig	In words	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level					
4.1.2A	1:1.5:3 (1 Cement: 1.5 coarse sand (zone-III) including manufactured sand derived from Recycled Concrete Aggregate(RCA) upto 25% : 3 graded stone aggregate 20 mm nominal size Recycled Concrete Aggregate (RCA) upto 25%).	cum	5			
15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge.					
15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	5			
278	Supplying and filling manufactured sand derived from Recycled Concrete Aggregate (RCA) at the identified location by Engineer-in-charge including transportation lead & lift	cum	3			
279	Supplying and filling Recycled Concrete Aggregate (RCA) 20 mm nominal size at the identified location by Engineer-in-charge including transportation lead & lift	cum	3			
Amount (Excluding GST) _____						
Add GST % _____						
Total Amount : _____						

Term and conditions:

- 1) The work should be carried out strictly as per the specifications and as per the directions of the Engineer-in-charge.
- 2) Time allowed for completion of work is 10 days from the date of issue of Work Order.

(Cont...2)



-2-

- 3) The rate shall include the cost of all labour, materials and all the operations involved as described in the specification of item and nothing extra shall be paid on whatsoever account.
- 4) The rate should be quoted both in figures and words which should include all taxes etc.
- 5) The rate should be applicable to all heights and leads and transportation of materials and tools etc.
- 6) Defect liability period 1 (One) year from the date of completion of the work
- 7) The payment shall be made as per actual execution and measurement at site.
- 8) The Income tax shall be deducted as per applicable and notified by Govt. of India.
- 9) In case of delay in completion of the contract, LD at 1/2 percent of the contract value per day of delay subject to the maximum of 10% of contract value/work order will be levied without assigning any reason unless extension is obtained in writing from the office on valid ground before completion date.


Executive Engineer

Copy to :

- 1) The Office of the Registrar,
- 2) Director CIT for uploading in the University website.
- 3) Notice Board.

कार्यकारी अभियंता/ Executive Engineer
इंजीनियरिंग अनुभाग/ Engineering Section
मौलाना आज़ाद नेशनल उर्दू यूनिवर्सिटी
Maulana Azad National Urdu University
गच्छिबौली, हैदराबाद - ५०००३२
Gachibowli, Hyderabad-500 032.